



End user Application

B V REDDY Chief Engineer Jacob Engineering India

June 14, 2012





1. Project Back ground

- 2. Challenges
- 3. Automation Solution Selection
- 4. RIO System (Selected)
- 5. System Built
- 6. Commissioning
- 7. Validation
- 8. Lessons learned



1. Project Back ground

DETAILS :-

Project : Multi product API facility Type : Green field Product : Bulk API Process : Batch production End User : Dr.Reddys Laboratories Ltd. Location : Hyderabad, India Year : 2012





Total : 4584 + 1040 = 5624



2. Challenges

The Automation solution has to be designed by keeping following in mind :-

- Area classification : Zone #1



- Available engineering resources (Maint.) a. Engineers
 - b. Expertise
- Time for execution
- Multi products
- Budget
- Scalability



3. Automation Solution Selection

Available options :

Conventional IO System – JB's, Marshaling panels etc..


Field Bus


- a. Technical expertise
- b. Engineering
- c. Flexibility
- d. More Digital I/O's

Remote I/O based system

(Hybrid systems)











4. RIO System (Selected)

Features

- Less wiring
- No need for marshalling distributors, cable racks, etc.
- Time saving due to reduced wiring
- No additional mechanical protection is needed to achieve the Ex-protection class
- High flexibility: quick and easy expansion
- Low engineering overhead
- Optimal diagnosis capabilities
- Cost saving over the complete life-cycle
- Optimized connection of valves



4. RIO System (Selected)

Buses Used :-

Profibus DP – The total R I/O's on Profibus VFD's on Profibus

ASI bus - All MCC related I/O's





Modbus - ESB's

Modbus



Ethernet I/P – All centrifuges for monitoring




5. System Built

- a. System configuration
- b. Main hardware components
- c. Software features



System Built - System configuration





System Built

- b. Main hardware components
- i. Delta V system Features
 - PSY & CPU Redundancy
 - Controller : MX



- Profibus I/O comm : Redundancy

Redundant Operation


The active and standby masters are connected to the segment at the redundant terminal block, supporting a simplex wiring scheme. Configuration of redundancy is not required as the DeltaV system automatically recognizes the redundant pair of cards and assigns device signal tags (DST) to the channels on the primary card.

Switchover time for redundant master is less than 100 ms






System Built - ASI BUS





- Intrinsically safe Profibus DP and ServiceBus
- Integrated Ex i power supply for up to 8 I/O modules
- System redundancy (Profibus standard) and media redundancy
- ServiceBus interface for fault diagnostics and Asset Management System
- LCD indicator for local display of diagnostic data, input and output values
- I/O Module including Communication Slaves can be replaced in Zone 1 / Div. 1 in operation (hot swap)











5. System Built - RIO details

- 8 channels for 2-wire HART transmitters (AI / AO)
- 16 channels for contacts and NAMUR proximity switches (EN 60947-5-6) DI
- 8 channels for Ex i / I.S. solenoid valves, piezo and booster valves DO

Intrinsically safe inputs Ex ia IIC Galvanic isolation between inputs and system Open-circuit and short-circuit monitoring for each field circuit Module can be replaced in operation (hot swap)















5. System Built - RIO details







5. System Built - HMI details

- 19" widescreen displays for Ex areas (resolutions: 1280 x 1024 / 1680 x 1050 / Full HD 1920 x 1080)
- For universal use, in particular pharmaceutics / chemistry / petrocł
- Brilliant picture quality through
- LED backlight technology
- Environmentally friendly through use
- Iead-, mercury- and cadmium-free d
- Data transmission via CAT7

or optical fibre cable (< 10,000 m)


SAFE AREA	ZONE 1 / 2 / 21 / 22
KVM USB	EX
PC TRANSMISSION UNIT	CAT7 < 150m / Fiber optic < 10km
	Ethernet





5. System Built - FEATURES


- Reactor Temp. control (Heating & Cooling)
- Solvent dispensing (Charging)
- Layer separation
- PW charging
- Reactor level/Volume monitoring
- S-88 batch standard implementation
- Recipe handling
- Data Acquisition
- Real time traceability The ES was connected to Intranet through firewall





5. System Built - Snap shots


DCS- Screen Snap Shots





5. System Built - Snap shots


DCS- Screen Snap Shots





5. System Built - Snap shots

DCS- Screen Snap Shots





5. System Built

Field Instrumentation

Mass/ Mag / Vortex flow meters Pressure Transmitters Temp.transmitters pH transmitters Oxygen transmitters RADAR level Transmitters Weighing systems Globe Control valves ON/Off Ball Valves Electronic Status Boards Conductivity transmitters (Layer separation)



5. COMMISSIONING

- Erection activity
- Field instruments erection
- Cable tray and laying
- DCS panel erection
- RIO panel erection with out modules
- RIO Power and comm cable laying
- RIO modules loading
- DCS panel power up
- RIO panel power up
- RIO comm establishment
- Field inst termination
- Soft wares loading
- Ready for FAT








7. VALIDATION

The following documents has been prepared and got approved during various phases of project to meet part 11 requirements :

- URS The detailed specifications for DCS.
- FRS The detailed process description along with flow charts and P & ID.
- FDS
- FAT (Hard ware & Soft ware)
- SAT (Hard ware & Soft ware)
- IQ
- OQ
- PQ





8. Lessons learned

- Controller wise I/O segregation to avoid load on controller
 - Which leads to re engineering
 - Re grouping of tags as per controller (Process)
- Controller loading It is very difficult to calculate in off line







THANK YOU